
CONSTRUCTION SPECIFICATION
CS-OR-003 STRUCTURE REMOVAL

003.1 SCOPE

The work shall consist of the removal, salvage, and disposal of structures (including fences) from the designated areas.

003.2 MARKING

Each structure or structure part (or designated area around the structure) to be removed will be marked with stakes, flags, paint, or other suitable method.

003.3 REMOVAL

Structures shall be removed to the extent and depth shown on the drawings or as designated by a qualified NRCS representative.

003.4 SALVAGE

Structures or structure parts that are designated to be salvaged shall be carefully removed and neatly placed in the specified or approved storage location. Salvaged structures that are capable of being disassembled shall be dismantled into individual members or sections. Such structures shall be neatly and systematically match marked with paint before disassembly. All connectors and other parts shall be marked to indicate their proper location within the structure and shall be fastened to the appropriate structural member or packed in suitable containers.

Material from fences designated to be salvaged shall be placed outside the work area on the property on which the fence was originally located. Fence wire shall be rolled into uniform rolls of suitable size and neatly piled with other salvaged materials. Posts and rails shall be neatly stacked.

003.5 DISPOSAL OF REFUSE MATERIALS

Refuse materials resulting from structure removal shall be disposed of in a manner and at locations specified in Section 003.6 of this specification or in an acceptable manner and at locations approved by the NRCS representative. Disposal by burning shall be in accordance with local rules and regulations.

003.6 ITEMS OF WORK AND CONSTRUCTION DETAILS