

STATEMENT OF WORK
Seasonal High Tunnel System for Crops (798)
Oregon

These deliverables apply to this individual practice. For other planned practice deliverables refer to those specific Statements of Work.

DESIGN**Deliverables**

1. Design documents that demonstrate criteria in NRCS practice standard have been met and are compatible with planned and applied practices.
 - a. Practice purpose(s) as identified in the conservation plan.
 - b. List of required permits to be obtained by the client.
 - c. Impacts on adjacent properties and structures.
 - d. Compliance with NRCS national and state utility safety policy (NEM Part 503-Safety, Subpart A-Engineering Activities Affecting Utilities 503.00 through 503.06).
 - e. Practice standard criteria-related computations and analyses to develop plans and specifications including but not limited to:
 - i. Location
 - ii. Outlet considerations (e.g. Water Quality and Quantity, Surface Drainage, Erosion)
 - iii. Construction operations
 - iv. Vegetation
 - v. Environmental considerations
2. Written plans and specifications including manufacturer's material lists, details, sketches, and drawings shall be provided to the client that adequately describes the requirements to install the practice and obtain necessary permits. Plans and specifications shall be developed in accordance with the requirements of conservation practice standard Seasonal High Tunnel System for Crops (Code 798).
3. Operation and Maintenance Plan.
4. Certification that the design meets practice standard criteria and comply with applicable laws and regulations.
5. Design modifications during installation as required.

INSTALLATION**Deliverables**

1. Pre-installation conference with client and contractor.
2. Verification that client has obtained required permits.
3. Staking and layout according to plans and specifications including applicable layout notes.
4. Installation inspection (according to inspection plan as appropriate).
 - a. Actual materials used
 - b. Inspection records
5. Facilitate and implement required design modifications with client and original designer.
6. Advise client/NRCS on compliance issues with all federal, state, tribal, and local laws, regulations and NRCS policies during installation.
7. Certification that the installation process and materials meets design and permit requirements.

CHECK OUT**Deliverables**

1. As-Built documentation
 - a. Extent of practice units applied
 - b. Drawings
 - c. Final quantities
2. Certification that the installation meets NRCS standards and specifications and is in compliance with permits (NEM Subpart A, 505.03(c) (1)).
3. Progress reporting.

STATEMENT OF WORK
Seasonal High Tunnel System for Crops (798)
Oregon

(Continued)

REFERENCES

1. Oregon NRCS Field Office Technical Guide (eFOTG), Section IV, Conservation Practice Standard – Seasonal High Tunnel System for Crops, 798
2. NRCS National Engineering Manual (NEM)
3. NRCS National Environmental Compliance Handbook
4. NRCS Cultural Resources Handbook
5. NRCS National Agronomy Manual